NOTE: DRAFT — overlay not released: build and measure one harness on the first board before release (VALIDATE_FIRST_BOARD)
NOTE: dimension convention: point-to-point between node reference planes (default — confirm)

X2 HSG-DTM-2S
load
cav 1: RD
cav 2: BK
orientation: wedgelock up

X1 HSG-DTM-2P
battery
cav 1: RD
cav 2: BK
orientation: wedgelock up

INSPECTION — IPC/WHMA-A-620 Class 2 (record on traveller)

1. tug test every crimped termination (spec pull values on the termination map)
2. secondary lock / wedgelock closed — visual, every connector
3. label text + position legible against this overlay
4. bend radius at folds and breakouts ≥ cable datasheet minimum
5. final length check against this overlay (tolerances per drawing)
6. program test: continuity + 500 V insulation

customer drawing: D-1004 rev B
board overlay rev: B-B date: 2025-11-03
program: ETHDTM-2025
change summary: initial generation from data model

0 100 200 mm — SCALE 1:1